M. P. MÖLLER Organ Factory

Pipe Organ No.	R-407	Date	April 24, 1951
For	UNION COMMUNITY METHODIST CHURCH, UNION, N. J.		
Action	Electro-Pneumatic	Console	Present
Casing No	Two Grilles by M.P. Moller, Inc.	Finish	No Change
Decorations	None	Motor	Present
Width of Key-bed	No Change	Stop Controls	No Change
No. Manuals	Two and Pedal	Wind Pressure	No Change
To be Completed	Soon as Possible	Blower Pipe furnished by	Purchaser

SPECIFICATIONS

FOR

REPAIRING AND REINSTALLING MOLLER ORGAN #4781

Supply and install two organ grilles 8'-0" high x 7'-3" wide.

Supply and install one set of swell shades and motor for 8'-0" high x 7'-3" wide tone opening.

Supply and install one 1'-6" x 2'-6" reservoir.

Replace 146 primary pouches.

Replace 370 inside type armatures.

Supply and install 1'-0" x 1'-0" wind junction box.

Supply and install new swell shade switch (roller type)

Recover 6 shade and bumper pneumatics.

Recover 12 coupler pneumatics.

Recover 1 reversible pneumatic

Install new bumper felt in pedal keyboard.

Releather all electro-pneumatic switches.

Tone-regulate, repitch and tune organ.

GENERAL

M. P. Moller, Inc. to furnish all labor, materials and drayage in connection with the above work.

Union Community Methodist Church to furnish adequate organ chambers to be approved by M. P. Moller, Inc. Also to furnish and install all electrical wiring from blower to console and from DC generator to each organ chamber and console.

5/11/51
HDO/mb