

M. P. MÖLLER Organ Factory

Pipe Organ No. 7240 Date August 7, 1945
 For THE MORAVIAN CHURCH, ALLENTOWN, PENNSYLVANIA
 Action Electro-pneumatic Console Detached - Birch
 Casing No. None Finish As per sample
 Decorations None Motor 3/4 H.P. Style 3-p-2421
 Width of Key-bed Standard Stop Controls Stop Key
 No. Manuals Two Wind Pressure 4"
 To be Completed as soon as possible Blower Pipe furnished by Purchaser
All Units

PITCH: A-440 @ 68° F

SPECIFICATIONS GREAT ORGAN

1	8'	Open Diapason.....45 Scale.....20 Zinc C.M.....73 Pipes
2	8'	Lieblch Gedeckt...Spec. Bass Sm Bdn. Treble.....85 "
3	8'	Viole Dolce.....60 Scale.....20 Zinc C.M.....85 "
4	4'	Flute.....From #2.....61 Notes
5	4'	Octave.....From #1.....61 "
6	4'	Fugara.....From #3.....61 "
7	2'	Piccolo.....From #2.....61 "
8	8'	Trumpet.....From #19.....61 Pipes
9		Chimes Prepared for

SWELL ORGAN

10	16'	Bourdon..T.C.....From #2.....49 Notes
11	8'	Diapason.....From #1.....61 "
12	8'	Lieblch Gedeckt...From #2.....61 "
13	8'	Viole Dolce.....From #3.....61 "
14	4'	Octave.....From #1.....61 "
15	4'	Flute.....From #2.....61 "
16	4'	Fugara.....From #3.....61 "
17	2-2/3'	Twelfth.....From #2.....61 "
18	2'	String Dolce.....From #3.....61 "
19	8'	Trumpet.....3 1/2" Scale.....61 "
20		One Blank Tablet
21		Tremulant

PEDAL ORGAN

22	16'	Bourdon, (1-12)....L.M.B.....20 From #2.....32 Notes
23	8'	Open Diapason.....From #1.....32 "
24	8'	Flute.....From #2.....32 "
25	8'	Viole.....From #3.....32 "

COUPLERS

26	Great to Pedal
27	Swell to Pedal
28	Swell to Great

MECHANICALS

Crescendo Indicator Lights

Organ grille to be supplied and installed by M. P. Möller
 Wood - Maple or Birch

ADJUSTABLE COMBINATIONS

(Operated by pistons placed under respective manuals)

Pistons No. 1-2-3-4

Affecting Full Organ

PEDAL MOVEMENTS

- 1 Balanced Expression Pedal
- 2 Balanced Grand Crescendo Pedal

Organ bench with music shelf

Concave Pedal

Electric blower, motor and generator of ample capacity.

Pipes of the present organ to become the property of M. P. Moller, Inc.
to be used as salvage to replace inventory needed to make new pipes.