M. P. MÖLLER Organ Factory

Pipe Organ No.	R-497	Date	May 5, 1954
For	FIRST PRESBYTERIAN CHURCH, WHEATON, ILL.		
Action	Electro-Pneumatic	Console	Present
Casing No.	None	Finish	No Change
Decorations	None	Motor	New motor, Blower & Orgelectra
Width of Key-bed	No Change	Stop Controls	Present
No. Manuals	Two & Pedal	Wind Pressure	No Change
To be Completed	Sept. 1, 1954	Blower Pipe furnished by	Purchaser

SPECIFICATIONS

FOR

MOVING AND ADDING TO MOLLER ORGAN OPUS 7076

(1) Dismantle, move and reinstall present organ in new chamber which is to be prepared by the Church. The Church supply and install high voltage wiring for blower and generator and to supply and install galvanized wind conductor between console, organ and blower.

(2) M. P. Moller, Inc. to supply and install new expression shades and action, approximately 4'-0" x 8'-0", for Nave tone opening and install new swell box, approximately 2'-0" x 6'-0", for Chancel opening.

(3) Install new 8 Trumpet 73 pipes and action.

(4) Install new 3'-0" x 5'-0" main reservoir.

(5) Install new 1-1/2 HP Kinetic blower, Style 3-P-2724, together with new 10-15 volt, 20 ampere, Orgelectra power unit.

5/12/54
HDO/mb