

M. P. MÖLLER Organ Factory

4854

Nov. 2, 1926

Pipe Organ No. _____ Date _____
 For _____ First Methodist Episcopal Church, Albion, Mich.,
 Action _____ Elec. _____ Detached 15' cable
 _____ Oak _____ Console _____
 Casing No. _____ Finish _____ Elec. _____
 _____ Gilt _____ Motor _____
 Decorations _____ Stop Keys _____
 Width of Key-bed _____ Stop Controls _____ 5"
 _____ Three _____
 No. Manuals _____ Wind Pressure _____ Church
 _____ August 25, 1927 _____
 To be completed _____ Blower pipe furnished by _____

SPECIFICATIONS

Organ front of casing and display pipes by factory
 Organ chamber by church
 Organ to be all under 5" wind pressure:
 A-440

GREAT ORGAN 73 Chest

1	8'	Open Diapason.....40 scale.....	61 Pipes
2	8'	Doppel Floete.....	73 "
3	4'	Flute Traverso.....From #5.....	61 Notes
4	4'	Principal.....From #20.....	61 "
5	8'	Melodia.....unit.....	73 Pipes
6	8'	Viola D' Gamba.....	73 "
7	8'	Tuba.....	73 "
		Tremulant	

SWELL ORGAN

8	16'	Bourdon.....unit.....	97 Pipes
9	8'	Open Diapason.....42 scale.....	73 Pipes
10	8'	Stopped Diapason....From #8.....	73 Notes
11	4'	Flute D'Amour.....From #8.....	61 "
12	2'	Piccolo.....From #8.....	61 "
13	8'	Salicional.....	73 Pipes
14	8'	Cornopean.....	73 "
15	8'	Oboe.....	73 "
16	4'	Violina.....From #13.....	61 Notes
17	8'	Vox Celeste.....Tenor C.....	61 Pipes
18	8'	Vox Humana.....S. S. B.....	61 "
		Tremulant	

CHOIR ORGAN

20	8'	English Open Diapason..41 scale.....	73 Pipes
21	8'	Melodia.....From #5.....	73 Notes
22	8'	Dulciana.....	73 Pipes
23	8'	Gamba.....From #6.....	73 Notes
24	8'	Clarinet.....	73 Pipes
25	8'	Unda Maris.....Tenor C.....	61 "
26	4'	Solo Flute.....From #25.....	61 Notes
27	4'	Dulcet.....From #22.....	61 "
		Tremulant	
		Celeste Harp.	49 Bars
		61 Chest ECHO ORGAN (Played from Great Organ)	
28	8'	Echo Flute.....Traverso scale.....	73 Pipes
29	8'	Vox Angelica.....60 scale.....	61 "
30	8'	Viole Celeste.....62 scale.....	61 "
31	8'	Vox Humana.....	61 "
32	4'	Forest Flute.....From #28.....	61 Notes
		Deagan Chimes.....	20 Bells
		Tremulant	

PEDAL ORGAN

34	32'	Diapason Resultant.....	32 Notes
35	16'	Open Diapason.....	32 Pipes
36	16'	Bourdon.....	44 "

PEDAL ORGAN (Continued)

37	16'	Lieblich Gedeckt.....	From #8.....	32 Notes
38	8'	Bass Flute.....	From #36.....	32 "
39	8'	Octave Bass.....	From #35.....	32 "

COUPLERS

40	Swell to Great 4'	54	Choir to Swell 8'
41	Swell to Great 8'	55	Choir to Swell 16'
42	Swell to Great 16'	56	Swell to Swell 4'
43	Choir to Great 4'	57	Swell to Swell 16'
44	Choir to Great 8'	58	Swell to Pedal 4'
45	Choir to Great 16'	59	Swell to Pedal 8'
46	Great to Great 4'	60	Great to Pedal 4'
47	Great to Great 16'	61	Great to Pedal 8'
48	Swell to Choir 4'	62	Swell Unison Off) <i>Choir to Pedal</i>
49	Swell to Choir 8'	63	Great Unison Off) in jambs right
50	Swell to Choir 16'	64	Choir Unison Off)
51	Choir to Choir 4'	65	All Couplers Cancel by Piston
52	Choir to Choir 16'	66	Echo "On" Great "off"
53	Choir to Swell 4'	67	Echo to Great

MECHANICALS

Great Tremulant
Swell Tremulant
Choir Tremulant
Crescendo Indicator

ADJUSTABLE COMBINATIONS

(Operated by pistons placed under respective manuals)

Pistons No. 1-2-3-4-5-6 & Cancel Affecting Great Organ
Pistons No. 1-2-3-4-5-6 & Cancel Affecting Swell Organ
Pistons No. 1-2-3-4-5-6 & Cancel Affecting Choir Organ
Pistons No. 1-2-3-4-5-6 & Cancel Affecting Pedal Organ
Pistons No. 1-2-3-4 & Cancel Affecting Full Organ, duplicated by studs on Toe Board.
Pedal to Manual "ON" and "OFF" Pistons in jambs left.

PEDAL MOVEMENTS

- 1 Great to Pedal Reversible
- 2 Balanced Swell Expression Pedal
- 3 Balanced Choir & Great Expression Pedals
- 4 Swell to Pedal Reversible
- 5 Sforzando Pedal, by stud & light indicator duplicated by manual piston.
- 6 Grand Crescendo Pedal (Beginning at the softest stop and drawing all stops including reeds & couplers in their order of power by a single movement of the foot. By reversing the movement all stops & couplers are canceled in their order.
Concave Radiating Pedals.

FURNISHED WITH ORGAN

Organ bench with music shelf
Electric motor, blower, generator, freight & drayage from factory to building & Installation.

11/16/26

ACZ

Checked by.....Date